



COUNTY OF ALAMEDA

ADDENDUM No.2

to

R2-15008 Santa Rita Jail Condenser Water System Upgrade

Specification Clarification/Modification and Recap of the Networking/Bidders Conferences
Held on Tuesday, September 8, 2015 @ 8:30 A.M.

This County of Alameda, General Services Agency (GSA), RFP/Q Addendum has been electronically issued to potential bidders via e-mail. E-mail addresses used are those in the County's Small Local Emerging Business (SLEB) Vendor Database or from other sources. If you have registered or are certified as a SLEB, please ensure that the complete and accurate e-mail address is noted and kept updated in the SLEB Vendor Database. This RFP/Q Addendum will also be posted on the GSA Contracting Opportunities website located at http://www.acgov.org/gsa/purchasing/bid_content/ContractOpportunities.jsp.



Alameda County is committed to reducing environmental impacts across our entire supply chain. If printing this document, please print only what you need, print double-sided, and use recycled-content paper.

County of Alameda, General Services Agency
Addendum No. 2

Responses to Written Questions

Q1) Can the cooling tower be stored in a different location for the County's abatement contractor to remove hazardous material abatement?

A1) **YES, prior to craning the unit off the roof, the contractor will indicate the areas on the cooling tower where the cooling tower will be cut in sections in order to crane the units off the roof. The county abatement contractor will abate any hazardous material prior to cutting the unit in pieces prior to removal. The contractor shall mobilize the cooling tower on the north side of the building maintenance warehouse located near CP52 (see picture below). The county abatement contractor will direct the work and prepare the area to receive the cooling tower and dispose of the tower when all hazardous material has been abated. Contractor shall coordinate all work with the County's abatement contractor.**

THE COUNTY ABATEMENT CONTRACTOR WILL DISPOSE OF THE COOLING TOWER AND ANY PIPING CONTAINING GASKETS; THEREFOR, THE CONTRACTOR WILL NOT NEED TO DISPOSE OF THE COOLING TOWER.

