ADDENDUM NO. 01

Issue Date: July 15, 2009

FROM: County of Alameda - GSA/TSD

1401 Lakeside Drive, Suite 800 Oakland, California 94612

Hadi Hadjarzadeh, Program Manager Phone (510) 220-3445 Fax (510) 208-3995

TO BIDDERS HIGHLAND HOSPITAL KORET Building Exhaust Fan and Waterproofing

ON: 1131 East 31st Street Oakland, California

THIS ADDENDUM is hereby made a part of the Project Specifications and Other Bidding and Contract Documents issued on June 19, 2020, on the subject work as though originally included therein. The following amendments, additions and/or corrections shall govern this work.

A01-1 REVISED DIVISION 00 – PROCUREMENT AND CONTRACTING REQUIREMETNS (Attached to this Addendum)

The following ADDED or REVISED Procurement and Contracting Requirements documents issued by and attached to this Addendum replace the documents of the same document number issued with the RFP and are hereby made a part of the Contract requirements. They shall be binding as though included in the original Project Manual.

Document Number	Document Title	Date
Document 00 01 10	Table of Contents	6/30/20
Document 00 21 19	ECOP GOALS Compliance Table (ECOP Form 101A,101B,102A,102B,102C)	1/6/14
Document 00 31 19	Existing Conditions Information	6/29/20
Document 00 73 49B	First Amendment to Project Stabilization/Community Benefits Agreement County of Alameda	6/9/20

Revisions are shown as follows: additions are <u>underlined</u>; deletions are struck through; and all affected portions of a document are clouded.

A01-2 REVISED DIVISION 01 - GENERAL REQUIREMENTS (Attached to this Addendum)

The following ADDED General Requirements documents issued by and attached to this Addendum replace the documents of the same document number issued with the RFP and are hereby made a part of the Contract requirements. They shall be binding as though included in the original Project Manual.

Document Number	Document Title	Date
Document 01 01 00	Summary of Work for Glass Replacement	6/30/20

ADDENDUM NO. 01

A01-3 REVISED SPECIFICATIONS (Attached to this Addendum)

The following REVISED Specification documents issued by and attached to this Addendum replace the documents of the same document number issued with the RFP and are hereby made a part of the Contract requirements. They shall be binding as though included in the original Project Manual.

Document Number	Document Title	Date
Document 07 92 00	Joint Sealants	6/30/20

Revisions are shown as follows: additions are clouded; deletions are struck through; and all affected portions of a document are clouded.

A01-4 OTHERS (Attached to this Addendum)

- A. Please see attached Pre-Bid Attendees List for the Highland Hospital Koret Building Exhaust Fan and Waterproofing Mandatory Pre-Bid Meeting (Alameda County GSA Project # 2043) held on July 7, 2020 at 2:00 PM.
- B. Receipts of Bids and Bid Opening is changed from July 17, 2020 to August 27, 2020 by 2:00 PM.
- C. Please see attached Alameda County Contractor Technical Assistance Program document for more information about the program. The information that was presented during the Mandatory Pre-Bid Meeting about the County's Contractor Technical Assistance Program (CTAP) is as follows:

Carol Henry, Program Manager <u>Carol@imwis.com</u> (510) 740-6922 ext. 710

CTAP@imwis.com

D. This project is under the PLA (Project Labor Agreement) and any project over a million dollar need to meet county requirement to have a PLA.

END OF ADDENDUM NO. 01 (Attachments follow)

'DOCUMENT 00 01 10

TABLE OF CONTENTS

This Table of Contents describes the documents provided to Bidders: Specifications and Other Bidding and Contract Documents for the Highland Hospital - Koret Building Exhaust Fan and Waterproofing Project. Please refer to the all Division 00, Division 01, Specifications, and Drawings in order to understand the complete requirements for the Project.

DIVISION 00 — PROCUREMENT AND CONTRACTING REQUIREMENTS

00 00 00 PROCUREMENT AND CONTRACTING REQUIREMENTS

INTRODUCTORY INFORMATION

00 01 01 **Project Title Page**

00 01 09 **Summary Bidding Calendar**

Table of Contents 00 01 10

00 01 15 **List of Drawings**

PROCUREMENT REQUIREMENTS

00 10 00 SOLICITATION

00 11 00 Advertisements and Invitations

00 11 16 **Notice to Bidders**

00 20 00 INSTRUCTIONS FOR PROCUREMENT

00 21 00 Instructions

00 21 13 **Instructions to Bidders**

Supplementary Instructions to Bidders – Enhanced Construction 00 22 19

Outreach Program

00 30 00 **AVAILABLE INFORMATION**

00 31 00 Available Project Information

00 31 19 **Existing Conditions Information**

00 40 00 PROCUREMENT FORMS AND SUPPLEMENTS

00 41 00 Bid Forms

00 41 13 **Bid Form – Stipulated Sum (Single-Prime Contact)**

00 43 00 Procurement Form Supplements

00 43 13 **Bid Security Form**

00 43 36 **Designated Subcontractors List**

00 45 00 Representations and Certifications

00 45 01 **Site-Visit Certification**

00 45 13 **Non-Collusion Affidavit**

00 45 26 **Worker's Compensation Certification**

00 45 46 Governmental Certifications

00 45 46.01 **Prevailing Wage and Related Labor Requirements**

Certification

00 45 46.04	Hazardous Materials Certification
00 45 46.06	Imported Materials Certification

CONTRACTING REQUIREMENTS

00 50 00	CONTRACTING FORMS AND SUPPLEMENTS
00 51 00	Notice of Award
00 51 1	Notice of Intent to Award
00 52 00	Agreement Forms
00 52 1	
	3.1 Debarment and Suspension Certification Form
	Notice to Proceed
00 56 00	Escrow of Bid Documentation
00 57 00	Escrow Agreement for Security Deposits in Lieu of Retention
	, , ,
	PROJECT FORMS
00 61 00	Bond Forms
00 61 1	Performance and Payment Bond Forms
00	61 13.13 Performance Bond Form
00	61 13.16 Payment Bond Form
00 65 00	Closeout Forms
	9 Certificate of Completion Forms
00	65 19.26 Final Settlement Certificate Form
00 65 3	36 Warranty Form
	•
00 70 00	CONDITIONS OF THE CONTRACT
00 72 00	General Conditions
00 72 1	3 General Conditions – Stipulated Sum (Single-Prime Contract)
00 73 00	Supplementary Conditions
00 73 1	3 Special Conditions
00 73 4	Project Stabilization/Community Benefits Agreement (PSCBA)
00 73 5	Project Stabilization/Community Benefits Agreement (PSCBA) Hazardous Materials Procedures and Requirements

<u>DIVISION 01 — GENERAL REQUIREMENTS</u>

01 00 00	GENERAL REQUIREMENTS
Q1\10\00v	Santanary
01 01 00	Summary of Work for Glass Replacement
01 11 00	Summary of Work
LUL	mmmm
01 20 00	PRICE AND PAYMENT PROCEDURES
01 22 00	Unit Prices and Alternates
01 26 00	Contract Modification Procedures
01 29 00	Payment Procedures
01 30 00	Administrative Requirements
01 31 00	Project Management and Coordination
01 31 19	Project Meetings
ALAMEDA CO	OUNTY GSA-TSD
Page 2 of 3	

	01 32 16 01 33 00	Schedules and Reports Submittal Procedures
01	40 00 01 41 00	QUALITY REQUIREMENTS Regulatory Requirements
	01 42 00	References
	01 42	13 Abbreviations and Acronyms
	01 42	16 Definitions and Reference Standards
	01 43 00	Quality Assurance – materials and equipment
	01 45 00	Quality Control
01	50 00	TEMPORARY FACILITIES AND CONTROLS
01	60 00	PRODUCT REQUIREMENTS
	01 62 00	Product Options and Substitutions
	01 65 00	Delivery, Storage and Handling
01	70 00	•
		Examination and Preparation
	01 71	8 8
		Execution
	01 73	
		Construction Waste Management
		Protecting Installed Construction
		Construction Closeout
		Closeout Submittals
	01 78	1
	01 78	
	01 78	39 Project Record Documents
01	90 00	LIFE CYCLE ACTIVITIES
01		Commissioning
	01 91	•

SPECIFICATIONS

Joint Sealants 07 92 00 09 96 53 **Elastomeric Coating**

DRAWINGS

KORET BUILDING EMERGENCY DEPARTMENT EXHAUST FAN **BUILDING K (Koret Building) EXTERIOR MAINTENANCE**



General Contractor Name:

ECOP GOALS

COMPLIANCE TABLE

SEE GOOD FAITH EFFORT (GFE) INSTRUCTIONS BEL	.OW ECOP Form 101A
ect Name:	

Project #	Project N	ame:					
Total Contract Amount (BI	0):						
ECOP GOALS: 60% Local (LBE FIRMS)							
Name (Prime or Subcontractor)	LBE Location (City)	License/Certification by	Lic Expiration Date mm/dd/yyyy	Work To Be Performed	Dollar Value of Contract	Auto Percent	
				TOTAL LBE			
				TOTAL LBE			

This form is required to provide LBE information for the project specified above.

LBE must have current and valid certification from acceptable agencies identified in Section 3.5 of the Supplemental Instruction to Bidders DOCUMENT 00 22 19 on the date bids are opened OR meet the Local definition in Section 3.1. Attach Copy of all certification and current and valid

business license issued by the County or a city within the County.

THIS FORM MUST BE SUBMITTED BY 2:00 p.m., TWO BUSINESS DAYS FOLLOWING THE BID OPENING TO THE GENERAL **SERVICES AGENCY, 1401 LAKESIDE DRIVE, SUITE 907, OAKLAND, CALIFORNIA 94612**

			ECOP GOALS: 2	0% Small (SLBE Firms	s)	2001 101111	
	Name (Prime or Subcontractor)	SLBE Location (City)	Certified By*	SLBE Cert Expiration Date	Work To Be Performed	Dollar Value of Contract	Auto Percent
TOTAL SLBE Total state Total					TOTAL SLBE		

This form is required to provide SLBE information for the project specified above.

SLBE must have current and valid certification from acceptable agencies identified in Section 3.5 of the Supplemental Instruction to Bidders

DOCUMENT 00 22 19 on the date bids are opened. SLBEs must meet the Local definition in Section 3.1. Attach Copy of all certification and current and valid business license issued by the County or a city with the County.

THIS FORM MUST BE SUBMITTED BY 2:00 p.m., TWO BUSINESS DAYS FOLLOWING THE BID OPENING TO THE GENERAL SERVICES

AGENCY, 1401 LAKESIDE DRIVE, **SUITE 907, OAKLAND, CALIFORNIA 94612**

ECOP Form 102A

			TABLE Continued		ECOP Form 10	ZA
ECOP GOALS: 15% Minority (MBE FIRMS)						
Name (Must be Subcontractor)	MBE Location (City)	Certified By*	MBE Cert Expiration Date	Work To Be Performed	Dollar Value of Contract	Auto Percent
,		,				
				TOTAL MBE		
1			I	HUTALMBE	İ	i l

TOTAL MBE This form is required to provide MBE information for the project specified above

MBE must have current and valid certification from acceptable agencies identified in Section 3.2 of the Supplemental Instruction to Bidders

DOCUMENT 00 22 19 as of the date bids are opened. Attach MBE certifications to this form.

Subcontractor participation to include manufacturers, suppliers and truckers.

THIS FORM MUST BE SUBMITTED BY 2:00 p.m., TWO BUSINESS DAYS FOLLOWING THE REQUEST FROM GSA TO THE GENERAL SERVICES AGENCY,
1401 LAKESIDE DRIVE, SUITE 907, OAKLAND, CALIFORNIA 94612

ECOP GOALS: 5% Woman (WBE FIRMS)						
Name (Must be Subcontractor)	WBE Location (City)	Certified By*	WBE Cert Expiration Date	Work To Be Performed	Dollar Value of Contract	Auto Percent
				TOTAL WBE		

This form is required to provide WBE information for the project specified above.

WBE must have current and valid certification from acceptable agencies identified in Section 3.2 of the Supplemental Instruction to Bidders

DOCUMENT 00 22 19 as of the date bids are opened. Attach WBE certifications to this form.

Subcontractor participation to include manufacturers, suppliers and truckers.

THIS FORM MUST BE SUBMITTED BY 2:00 p.m., TWO BUSINESS DAYS FOLLOWING THE REQUEST FROM GSA TO THE GENERAL **SERVICES AGENCY,**

1401 LAKESIDE DRIVE, SUITE 907, OAKLAND, CALIFORNIA 94612

GOOD FAITH EFFORT INSTRUCTIONS CHECKLIST ECOP FORM 102C See County of Alameda Supplementary Instructions to Bidders Section 00 22 19 for complete Good Faith Effort requirements summarized below. See Required Good Faith Efforts for acceptable documentation to support that GFEs (1-9 below) were made. Indicate Yes or No with "X" and type in requested documentation in right column. Yes No 1. Attended pre-solicitation/pre-bid meetings held by GSA If yes, note documentation: 2. Identified and selected items for performance by MWSLBE's If yes, note documents submitted to support Items identified and selected: 3. Advertised not <10 calendar days before bids opened in If yes, note publications and attach advertisement: publication specified by GSA per GSA specification 4. Written notice to number of MWSLBEs specified on bid speci Note documentation and attach written notice(s) -5. Follow-up initial solicitations of interest with MWSLBEs If Yes, note documentation and attach proof of follow-up: 6. Provided interested MWSLBEs with information about plans If Yes, note documentation and attach proof of response specs and requirements 7. Requested assistance from MWSLBE community If Yes, note documents and attach proof of requests (date, organization name, contact name, phone organizations that provide assistance in recruitment and number, summary) placement of MWSLBEs 8. Negotiated in good faith w/MWSLBEs and did not If Yes, note documentation and attach proof of negotiations/acceptance unjustifiably reject MWSBLE bids 9. Advised and made efforts to assist interested MWSLBEs in If Yes, note documents and attach proof of assistance obtaining bonds, lines of credit or insurance **ACCEPTABLE DOCUMENTATION TO SUPPORT GFE's** REQUIRED GOOD FAITH FEFORTS **EXAMPLES OF ACCEPTABLE DOCUMENTATION** The bidder attended mandatory pre-solicitation or pre-bid meetings that were Copy of pre-bid meeting sign in sheet (which is e-mailed to attendees and available on scheduled by the local agency to inform all bidders of the ECOP requirements for the project County Current Contracting Opportunities website listed below). The name of the firm must for which the contract will be awarded. http://www.acaov.ora/asa_app/asa/purchasina/bid_content/contractopportunities.isp The bidder identified and selected specific items of the project for which the contract Copy of advertisements, certified letters, successfully completed faxes and/or other notices will be awarded to be performed by M/W/S/LBEs to provide an opportunity for participation to M/W/S/LBEs with selected specific items identified. by those enterprises. The bidder advertised, not less than ten (10) calendar days before the date the bids are Copy of advertisements placed showing publication name and date, and dated receipts. opened, in one or more local daily or weekly newspapers, trade association publications. Dated receipt with ad copy. minority or trade oriented publications, trade journals, or other media specified by the local agency for M/W/S/LBEs that are interested in participating in the project. The bidder provided written notice of his or her interest in bidding on the contract to the • Copy of dated notice, complete distribution list(s) and evidence of distribution (proof of number of M/W/S/I BEs required to be notified by the project specifications not less than ten faxes, e-mails sent etc.) Undelivered faxes do not count toward the effort to meet the minimum requirement (10) calendar days prior to the opening of bids. The minimum number of M/W/S/LBE firms required to be notified is three (3) for each item of the project selected to be performed by a • Trades and specialties, in addition to M/W/S/LBE designation, must be clearly identified to M/W/S/LBE, where a M/W/S/LBE subcontractor has not been secured for that item. The neet the minimum requirement by using certification letter or source documentation bidder may utilize the list of certified minority or women business enterprises prepared by the Department of Transportation pursuant to Section 14030.5 of the Government Code and the list of local business enterprises in the on-line County Small Local Emerging Business (SLEB) Vendor Query System located at: app/qsa/sleb/query/slebmenu.jsp The bidder followed up initial solicitations of interest by contacting the enterprises to • Successfully completed telephone log containing specific dates, name of caller, person determine with certainty whether the enterprises were interested in performing specific items contacted and comments (i.e., why not bidding, information sent to/date, etc.) of the project. The bidder provided interested M/W/S/LBEs with information about the plans, • Copy of published advertisements, letters, successfully completed faxes, etc. with specifications, and requirements for the selected subcontracting or material supply work, M/W/S/LBE name/contact information including the required information or directions on how to obtain it and the date the information was provided Agenda, meeting notes, etc. including specific topics discussed, M/W/S/LBE firm names and contact persons in attendance that received information, and the location and date The bidder requested assistance from local and small business and minority and women Copy of dated written request and response (letter, successfully completed fax, e-mail, etc.) or 2nd written request to follow-up, if needed. Contractor must attempt to contact at least community organizations; local and small, minority and women contractor groups, local, state, or federal M/W/S/LBE assistance offices, or other organizations that provide assistance in two organizations. recruitment and placement of M/W/S/LBEs. Phone log is not acceptable. The bidder negotiated in good faith with the M/W/S/LBEs and did not unjustifiably reject · Copies or list of all bids and a spreadsheet listing all bids with firm name, contact person, bid as unsatisfactory bids prepared by any M/W/S/LBEs as determined by GSA. items(s), bid price, M/W/S/LBE classification, and comments re: selection or rejection M/W/S/LBE bids accepted and included in bid response Where applicable, the bidder advised and made efforts to assist interested M/W/S/LBEs • Copy of advertisements or other notices with specifics referencing willingness to assist in obtaining bonds, lines of credit, or insurance required by either the GSA or the contractor. Agenda, meeting notes including presenter's name and title, specific topics discussed, hand outs etc., name of M/W/S/LBE firms in attendance, contact persons who received advice, ocation and date advice was provided

DOCUMENT 00 31 19

EXISTING CONDITIONS INFORMATION

1. Summary

ALAMEDA COUNTY GSA-TSD

This document describes existing conditions at or near the Project, and use of information available regarding existing conditions. This document is **not** part of the Contract Documents. See General Conditions for definition(s) of terms used herein.

2. Reports and Information on Existing Conditions

- 2.1. Documents providing a general description of the Site and conditions of the Work may have been collected by County its consultants, contractors, and tenants. These documents may include previous contracts, contract specifications, tenant improvement contracts, as-built drawings, utility drawings, and information regarding underground facilities.
- 2.2. Information regarding existing conditions may be inspected at the County offices or the Construction Manager's offices, if any, and copies may be obtained at cost of reproduction and handling upon Bidder's agreement to pay for such copies. These reports, documents, and other information are **not** part of the Contract Documents.
- 2.3. Information regarding existing conditions may also be included in the Project Manual, but shall **not** be considered part of the Contract Documents.
- 2.4. The reports and other data or information regarding existing conditions and underground facilities at or contiguous to the Project are the following:
 - 2.4.1. Hazardous Material Reports described are not part of the Contract Documents. However, for Bidder's convenience, a copy of the surveys have been provided with the Project Manual. Reports are provided immediately following this document.
 - Project: R1207159; Highland Hospital, 1411 East 31st Street, 2.4.1.1. Oakland, CA EML ID: 2403939
 - 2.4.1.2. Project: R1197G03; Highland Hospital/1411 East 31st St./Oakland, CA., K. Bldg. EML ID: 2403934
 - 2.4.1.3. Project: R1197G03; Highland Hospital, 1411 East 31st Street, Oakland, CA EML ID: 2403937
 - Project: R1207159; Highland Hospital/1411 East 31st St./Oakland, 2.4.1.4. CA. EML ID: 2403936

EXISTING CONDITIONS INFORMATION

(updated 6/29/20)

DOCUMENT 00 31 19 Page 1 of 3

- 2.4.1.5. <u>2.4.1.1 Limited Asbestos & Lead Survey Report (Terracon Project</u> No. R1197G03) by Terracon Consultants, Inc. dated 6/17/20
- 2.4.1.6. <u>2.4.1.2 Limited Asbestos & Lead Survey Report (Terracon Project</u> No. R1207159) by Terracon Consultants, Inc. dated 6/17/20

3. Use of Information

- 3.1. Information regarding existing conditions was obtained only for use of County and its consultants, contractors, and tenants for planning and design and is **not** part of the Contract Documents.
- 3.2. County does not warrant, and makes no representation regarding, the accuracy or thoroughness of any information regarding existing conditions. Bidder represents and agrees that in submitting a bid it is not relying on any information regarding existing conditions supplied by County.
- 3.3. Under no circumstances shall County be deemed to warrant or represent existing above-ground conditions, as-built conditions, or other actual conditions, verifiable by independent investigation. These conditions are verifiable by Contractor by the performance of its own independent investigation, which Contractor must perform as a condition to bidding, and Contractor should not and shall not rely on this information or any other information supplied by County regarding existing conditions.
- 3.4. Any information shown or indicated in the reports and other data supplied herein with respect to existing underground facilities at or contiguous to the Project may be based upon information and data furnished to County by the County's employees and/or consultants or builders of such underground facilities or others. County does not assume responsibility for the completeness of this information, and Bidder is solely responsible for any interpretation or conclusion drawn from this information.
- 3.5. County shall be responsible only for the general accuracy of information regarding underground facilities, and only for those underground facilities that are owned by County, and only where Bidder has conducted the independent investigation required of it pursuant to the Instructions to Bidders, and discrepancies are not apparent.

4. Investigations/Site Examinations

4.1. Before submitting a Bid, each Bidder is responsible for conducting or obtaining any additional or supplementary examinations, investigations, explorations, tests, studies, and data concerning conditions (surface, subsurface, and underground facilities) at or contiguous to the Site or otherwise, that may affect cost, progress, performance, or furnishing of Work or that relate to any aspect of the means, methods, techniques, sequences, or procedures of construction to be employed by Bidder and safety

ALAMEDA COUNTY GSA-TSD

EXISTING CONDITIONS INFORMATION (updated 6/29/20)

Page 2 of 3 DOCUMENT 00 31 19

- precautions and programs incident thereto or that Bidder deems necessary to determine its Bid for performing and furnishing the Work in accordance with the time, price, and other terms and conditions of the Contract Documents.
- 4.2. On request, County will provide each Bidder access to the Site to conduct such examinations, investigations, explorations, tests, and studies, as each Bidder deems necessary for submission of a Bid. Bidders must fill all holes and clean up and restore the Site to its former condition upon completion of its explorations, investigations, tests, and studies. Such investigations and Site examinations may be performed during any and all Site visits indicated in the Notice to Bidders and only under the provisions of the Contract Documents, including, but not limited to, proof of insurance and obligation to indemnify against claims arising from such work, and County's prior approval.

END OF DOCUMENT

Page 3 of 3 DOCUMENT 00 31 19

Limited Asbestos & Lead Survey Report

Highland Hospital
1411 East 31st Street
Exterior Facade
Oakland, California

June 17, 2020 Terracon Project No. R1197G03

Prepared for:

Cymbre Potter
Vanir Construction Management, Inc.
1411 East 31st Street B1 Office
Oakland, CA 94602

Prepared by:

Terracon Consultants, Inc. 1466 66th Street Emeryville, California 94608 510-547-7771

Report Prepared by:		Annabelle Call
	Industrial Hygienist, CAC # 12-4856	
Report Reviewed by:	Karin Schroete	Karin Schroete
	Project Manager CAC #92-0772, CDPH #2228	

Offices Nationwide Employee-Owned Established in 1965 terracon.com



Limited Asbestos & Lead Survey Report

Vanir Construction Management, Inc. Highland Hospital 1411 East 31st Street Exterior Façade Sampling Oakland, California

Scope of Work

The following is a report of a limited asbestos and lead survey conducted by John Alexander, Certified Asbestos Consultant (CAC) and California Department of Public Health (CDPH) Lead Inspector/Assessor with Terracon Consultants, Inc. (Terracon). The survey was performed on May 11, 2020 on Levels 4, 5, 6 and 8 of the K Building at Highland Hospital located in Oakland, California.

Terracon was asked to limit the sampling to the materials that will be impacted by the scheduled work which included the replacement of the exterior sealant at the façade and roof and the repainting of the exterior plaster. No other suspect materials elsewhere in the building were sampled.

Results

Please see the attached laboratory results and chain of custody for sample material and location details.

Five (5) homogeneous suspect asbestos-containing materials (ACMs) were identified during the survey. The samples were analyzed using polarized light microscopy (PLM) techniques in accordance with methodology approved by the U.S. Environmental Protection Agency (EPA). As set forth in the Code of Federal Regulations, 40 CFR Part 763, Appendix A to Subpart F, Section 1.2 and 1.7.2.4, the lower limit of reliable detection for asbestos using the PLM method is approximately one percent (1%) by volume.

Asbestos was not detected in the sampled materials. A summary of the sample results is provided in the following table.

TABLE I NON-ASBESTOS CONTAINING MATERIALS

Material Description	General Sample Locations	Sample Results
	Level 5 G5 Column	
	Level 5 E1 Column	
	Level 4 E1 Wall	
	Level 4 A1.7 Wall	
Sterre	Level 6 C1 6.7 Wall	Mana Data da I
Stucco	Level 6 F5 Wall	None Detected
	Level 8 Roof B1, 5.7 Wall	
	Level 8 Roof C3 Wall	
	Level 8 Roof F2 Wall	
	Level 8 Roof E5 Wall	
Exterior White Window Scalart (Frame to	Level 5 G5 Column	
Exterior White Window Sealant (Frame to	Level 4 A, 51 Wall	None Detected
Building)	Level 6 F5 Wall	
Estados Districtos Content (Estados A	Level 5 G5 Column	
Exterior Black Window Sealant (Frame to Glass)	Level 5 A, 51 Wall	None Detected
	Level 6 F5 Wall	
Beige Elastomeric Paint	Vallecito Wall	None Detected
	14 th Avenue Wall	None Detected
Decorative Plaster with Grout	Vallecito / 14 th Column	None Detected

Any additional materials found during construction activities and not identified in this survey report should be assumed to be ACM.

One (1) paint sample was submitted for lead analysis. The sample was analyzed for lead content using the Flame Atomic Absorption spectroscopy in accordance to EPA Method SW846-3050B-7420. When "<" appears in the lead sample report, it should be interpreted as meaning below analytical detection limit.

The sample did not contain lead in detectable concentrations as shown in Table II below.

TABLE II LEAD IN PAINT

Sample Number	Description/Location of Sample	Results mg/kg (ppm)
Pb-01	Beige Paint / Concrete Wall Vallecito Place	<39 ppm

mg/kg - milligrams per kilogram, ppm - parts per million

Limited Asbestos & Lead Survey Report Vanir Construction Management, Inc. Highland Hospital 1411 East 31st Street Exterior Facade Oakland, California

Limitations

Our services consist of professional opinions, conclusions and recommendations that are made in accordance with generally accepted consulting standards, principles and practices. Reasonable attempts have been made to ensure that the report is complete and accurate with respect to Terracon's authorized scope of work. Terracon assumes no liability for damages, which might result from errors contained in the report or conditions, which the report fails to disclose. The quantity of samples, sample locations, and analyses performed were selected to provide analytical data to document and evaluate current site conditions. The reporting of bulk analytical results is presented as estimates resulting from analysis by EPA-approved methods.

The information provided in this report is not intended to be used as a biddable document for abatement purposes.



Appendix 1:

Laboratory Results and Chain of Custody - Asbestos





Report for:

Eric Dyer, Ms. Karin Schroeter Terracon Consultants, Inc. - Emeryville 1466 66th Street Emeryville, CA 94608

Regarding: Project: R1197G03; Highland Hospital/1411 East 31st St./Oakland, CA., K. Bldg.

EML ID: 2403934

Approved by:

Dates of Analysis: Asbestos PLM: 05-14-2020

Approved Signatory Amin Suliman

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267) NVLAP Lab Code 200728-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins EMLab P&K ("the Company") shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Lab ID-Version †: 11464497-1

6000 Shoreline Ct, Ste 205, So. San Francisco, CA 94080

(866) 888-6653 Fax (623) 780-7695 www.emlab.com

Date of Sampling: 05-11-2020 Date of Receipt: 05-11-2020 Date of Report: 05-14-2020

Client: Terracon Consultants, Inc. - Emeryville C/O: Eric Dyer, Ms. Karin Schroeter

Re: R1197G03; Highland Hospital/1411 East 31st St./ Oakland, CA., K. Bldg.

ASBESTOS PLM REPORT

Total Samples Submitted: 22

Total Samples Analyzed: 22

Total Samples with Layer Asbestos Content > 1%: 0

Location: 1A, Stucco; level 5 G5 column	Lab ID-Version‡: 11464496-1
Sample Layers	Asbestos Content
Gray Stucco	ND
Sample Composite Homogeneity:	Poor

Location: 1B. Stucco: level 5 GE column

Escation: 1B, Stuces, level 5 GE column	Eur IP Version 4. 11 10 1157 1
Sample Layers	Asbestos Content
Gray Stucco	ND
Sample Composite Homogeneity:	Poor

Location: 1C, Stucco; level 4 E1 wall	Lab ID-Version‡: 11464498-1
Sample Layers	Asbestos Content
Gray Stucco	ND
Sample Composite Homogeneity:	Poor

Location: 1D Stucco: level 4 A1 7 wall

Location: 1D, Stucco; level 4 A1.7 wall	Lab ID-Version‡: 11464499-1
Sample Layers	Asbestos Content
Gray Stucco	ND
Sample Composite Homogeneity:	Poor

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. Eurofins EMLab P&K reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

 \ddagger A "Version" indicated by -"x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

EMLab P&K, LLC EMLab ID: 2403934, Page 2 of 7

Lab ID-Version‡: 11464500-1

Lab ID-Version : 11464501-1

Lab ID-Version : 11464502-1

6000 Shoreline Ct, Ste 205, So. San Francisco, CA 94080

(866) 888-6653 Fax (623) 780-7695 www.emlab.com

Date of Sampling: 05-11-2020 Date of Receipt: 05-11-2020 Date of Report: 05-14-2020

Client: Terracon Consultants, Inc. - Emeryville C/O: Eric Dyer, Ms. Karin Schroeter

Re: R1197G03; Highland Hospital/1411 East 31st St./

Oakland, CA., K. Bldg.

ASBESTOS PLM REPORT

Location: 1E, Stucco; level 6 C1.6.7 wall

Sample Layers	Asbestos Content
Gray Stucco	ND
Sample Composite Homogeneity: Poor	

Location: 1F. Stucco: level 6 F5 wall

Sample Layers	Asbestos Content
Gray Stucco	ND
Sample Composite Homogeneity: Poor	

Location: 1G, Stucco; level 8 roof B1 5.7 wall

Sample Layers	Asbestos Content
Gray Stucco	ND
Sample Composite Homogeneity:	Poor

Location: 1H, Stucco; level 8 roof C3 waLL	Lab ID-Version‡: 11464503-1
Sample Layers	Asbestos Content
Gray Stucco	ND
Sample Composite Homogeneity: Poor	

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. Eurofins EMLab P&K reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

Lab ID-Version : 11464504-1

6000 Shoreline Ct, Ste 205, So. San Francisco, CA 94080

(866) 888-6653 Fax (623) 780-7695 www.emlab.com

Date of Sampling: 05-11-2020 Date of Receipt: 05-11-2020 Date of Report: 05-14-2020

Client: Terracon Consultants, Inc. - Emeryville C/O: Eric Dyer, Ms. Karin Schroeter

Re: R1197G03; Highland Hospital/1411 East 31st St./

Oakland, CA., K. Bldg.

ASBESTOS PLM REPORT

Location: 1I, Stucco; level 8 roof F2 wall

Sample Layers	Asbestos Content
Gray Stucco	ND
Sample Composite Homogeneity: Poor	

Location: 1J, Stucco; level 8 roof E5 wall	Lab ID-Version‡: 11464505-1
Sample Layers	Asbestos Content
Gray Stucco	ND
Sample Composite Homogeneity:	Poor

Location: 2A, Exterior white window sealant (frame to building); level 5 G5 column

Lab	ID- V	ersion ₄ :	11404300-1

Sample Layers	Asbestos Content	
White Sealant	ND	
Sample Composite Homogeneity: Moderate		

Location: 2B, Exterior white window sealant (frame to building); level 4 A.5.1 wall

Sample Layers	Asbestos Content
White Sealant	ND
Sample Composite Homogeneity: Moderate	

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. Eurofins EMLab P&K reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

6000 Shoreline Ct, Ste 205, So. San Francisco, CA 94080

(866) 888-6653 Fax (623) 780-7695 www.emlab.com

Client: Terracon Consultants, Inc. - Emeryville C/O: Eric Dyer, Ms. Karin Schroeter

Re: R1197G03; Highland Hospital/1411 East 31st St./

Oakland, CA., K. Bldg.

Date of Sampling: 05-11-2020 Date of Receipt: 05-11-2020 Date of Report: 05-14-2020

ASBESTOS PLM REPORT

Location: 2C, Exterior white window sealant (frame to building); level 6 F5 wall

Lab ID-Version : 11464508-1

Sample Layers	Asbestos Content
White Sealant	ND
Sample Composite Homogeneity:	Moderate

Location: 3A, Exterior black window sealant (frame to glass); level 5 G5 column

Lab ID-Version 1: 11464509-1

Sample Layers	Asbestos Content
Black Sealant	ND
Sample Composite Homogeneity: Poor	

Location: 3B, Exterior black window sealant (frame to glass); level 5 A.5 1 wall

Lab ID-Version 1: 11464510-1

Sample Layers	Asbestos Content
Black Sealant	ND
Sample Composite Homogeneity: Poor	

Location: 3C, Exterior black window sealant (frame to glass); level 6 f5 WALL

Lab ID-Version‡: 11464511-1

Sample Layers	Asbestos Content
Black Sealant	ND
Sample Composite Homogeneity:	Poor

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. Eurofins EMLab P&K reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

Lab ID-Version : 11464512-1

Lab ID-Version : 11464514-1

Lab ID-Version 1: 11464515-1

6000 Shoreline Ct, Ste 205, So. San Francisco, CA 94080

(866) 888-6653 Fax (623) 780-7695 www.emlab.com

Client: Terracon Consultants, Inc. - Emeryville C/O: Eric Dyer, Ms. Karin Schroeter

Re: R1197G03; Highland Hospital/1411 East 31st St./

Oakland, CA., K. Bldg.

Date of Sampling: 05-11-2020 Date of Receipt: 05-11-2020 Date of Report: 05-14-2020

ASBESTOS PLM REPORT

Location: 4A, Beige elastomeric paint; vallecito place wall

Sample Layers	Asbestos Content
Beige Paint	ND
Sample Composite Homogeneity: Poor	

Location: 4B, Beige elastomeric paint; vallecito place w	all Lab ID-Version‡: 11464513-1
Sample Layers	Asbestos Content
Beige Paint	ND
Sample Composite Homogeneity:	Poor

Location: 4C, Beige elastomeric paint; 14th avenue wall

Sample Layers	Asbestos Content
Beige Paint	ND
Sample Composite Homogeneity: Poor	

Location: 5A. Decorative plaster with grout: vallectito/14th column

Sample Lavers	Asbestos Content	
Yellow Plaster	ND	
Grout	ND	
Sample Composite Homogeneity: Poor		

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. Eurofins EMLab P&K reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

Lab ID-Version‡: 11464516-1

Lab ID-Version 1: 11464517-1

6000 Shoreline Ct, Ste 205, So. San Francisco, CA 94080

(866) 888-6653 Fax (623) 780-7695 www.emlab.com

Date of Sampling: 05-11-2020 Date of Receipt: 05-11-2020 Date of Report: 05-14-2020

Client: Terracon Consultants, Inc. - Emeryville C/O: Eric Dyer, Ms. Karin Schroeter

Re: R1197G03; Highland Hospital/1411 East 31st St./ Oakland, CA., K. Bldg.

ASBESTOS PLM REPORT

Location: 5B, Decorative plaster with grout; vallectito/14th column

Sample Layers	Asbestos Content
Yellow Plaster	ND
Grout	ND
Sample Composite Homogeneity: Poor	

Location: 5C. Decorative plaster with grout: vallectito/14th column

200mion 0 0, 2000 min prosess, various of 1 min obtaining		
Sample Layers	Asbestos Content	
Yellow Plaster	ND	
Grout	ND	
Sample Composite Homogeneity: Poor		

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. Eurofins EMLab P&K reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

 \ddagger A "Version" indicated by -"x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

EMLab P&K, LLC

Terracon

***E-MAIL R PM - S. Stein spsteiner@terracon	.com kmschroeter@terracon.com kmpilgrim@terracon.co	om PLM Analysis (Analyze all samples)
PM- M. Benefic		
□PM- D. Block David block@terrace		nt d thill d
roject Name/ Add	ress/ Building No. Tigh and tospita	East 3/st Speel Convent
roject# R119	7603 Sampled By: John ARKANO	Sampling Date: 5/11/20 K Blo
ample(s) sent to:	□ MAL □ ASB TEM □ EMLAB □ Other	
AT Rush	☐ 24HRS ☐ 48HR ☐ 3-5 days	
HM#	Material Description Styce a	
Sample ID	Sample Location & Material Location	Quantity:
IA	Level 5 65 Colymn	
IR	Level 5 El Colymn	
10	Level 4 E. Wall	
HM#	Material Description:	
Sample ID	Sample Location & Material Location	Quantity:
17	Level 4 Alo7 Wall	
	5000	
16	Level 6 F3 Wall	
HM#	Material Description: Sample Location & Material Description	Quantity:
Sample ID	1 0 0 F DI [7 1/4]	
16	11 1 2 4 5 6 2 1.///	
1	Level 8 Roof C3 Wally	
-	Level 8 Kut +2 Wall	
HM#	Material Description:	Quantity:
Sample ID	Sample Location & Material Location	0
7	- Level 8 Rut = 5 Wall	024
		0.3
		2403934
HM#	Material Description:	
Sample ID	Sample Location & Material Location	Quantity:
		1/2
Relinquished By:	T. Alexaul Signature:	Date/Time: 5/1//20
Received By:	Signature:	Date/ Time: 5/1/20/2
Relinquished By:	Signature:	Date/Time: /
Received By:	Signature:	Date/Time:



***E-MAIL R PM - S. Stein spsteiner@terracon PM- M. Benefi msbenefield@terraco PM- D. Blocd David.block@terraco Project Name/ Add Project#	Manage M	ACM BULK SAMPLE DATA SHEET PLM Analysis (Analyze all samples) Stop Analysis at First Positive Point Count Analysis (400-point)
Sample(s) sent to:	□ MAL □ ASB TEM □ EMLAB □ Other □ 24HRS □ 48HR □ 3-5 days	
HM# 1	Material Description Fxehron White Window	Sealant (Frame to BuildA
Sample ID	Sample Location & Material Location	Quantity:
0.4	7 0 - 0	
20	Total I A FI	
7.8	Level Till III	
20	Level 6 +5 Wall	11 Part 1/5 1
нм# 3	Material Description: Exemp Black W	Quantity: Glara
Sample ID	Sample Location & Material Location	Quantity: Glass
3A	Level 5 65 Columb	
38	Leve 15 A.5 Wall	
30	Level 6 F5 Wall	
нм# +	Material Description: Beine Elastomenic /	giht
Sample ID	Sample Location & Material Location	Quantity:
4A 4R 4C	Vallecito Place Wall Vallecito Place Wall 14th Avenue Wall	
HM# 3		ith Gront
Sample ID	Sample Location & Material Location	Quantity:
5A 58	Vallecto/Atthe Colynn Vallecta/Atthe Colynn	002
50	Vallecita/ 14th Column	403
HM#	Material Description:	v ≡
Sample ID	Sample Location & Material Location	Quantity: 3
Relinquished By:	Signature: Signature:	Date/Time: 5/1/20 Date/Time: 5/1/20 /23
Relinquished By:	Signature:	Date/Time:
Received By:	Signature:	Date/Time:



Appendix 2:

Laboratory Results and Chain of Custody - Lead





Report for:

Eric Dyer, Ms. Karin Schroeter Terracon Consultants, Inc. - Emeryville 1466 66th Street Emeryville, CA 94608

Regarding:

Project: R1197G03; Highland Hospital, 1411 East 31st Street, Oakland, CA

EML ID: 2403937

Approved by:

Dates of Analysis:

Lead - Flame AA: 05-12-2020

Technical Manager Andrew Ikeda

Indus Heda

Service SOPs: Lead - Flame AA (EM-BC-S-8443) AIHA-LAP, LLC accredited service, Lab ID #178697

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. Due to the nature of the analyses performed, field blank correction of results is not applied. The results relate only to the samples as received. Sample size, as it relates to Wipe samples only, is supplied by the client.

Eurofins EMLab P&K ("the Company") shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Eurofins EMLab P&K's LabServe® reporting system includes automated fail-safes to ensure that all AIHA-LAP, LLC quality requirements are met and notifications are added to reports when any quality steps remain pending.

17461 Derian Ave, Suite 100, Irvine, CA 92614

(866) 888-6653 Fax (623) 780-7695 www.emlab.com

Client: Terracon Consultants, Inc. - Emeryville

C/O: Eric Dyer, Ms. Karin Schroeter

Re: R1197G03; Highland Hospital, 1411 East 31st Street, Oakland, CA

Date of Sampling: 05-11-2020 Date of Receipt: 05-11-2020 Date of Report: 05-13-2020

LEAD: FLAME ATOMIC ABSORPTION SPECTROMETRY

Location:	Pb-1: Beige concrete wall, Vallecito Place wall
	·
Comments (see below)	A
Lab ID-Version‡:	11464282-1
Analysis Date:	05/12/2020
Sample type	Paint Chip sample
Method*	NIOSH 7082 & EPA 7000B modified
† Method Reporting Limit	39 ppm
Sample size	0.2556 grams
§Total Lead Result	< 39 ppm

Comments: A) The relative percent difference of the matrix duplicate pair was above control limits. The laboratory control sample and matrix blank were both within control limits and validated the batch.

Sample results have not been corrected for blank values.

Bulk samples are not covered under the AIHA-LAP, LLC service accreditation.

Wipe samples must meet ASTM E1792 criteria. Method Reporting Limits may not be valid for non-ASTM E1792 wipe samples.

- † The Method Reporting Limit is the minimum concentration of Lead that the laboratory can confidently detect in the sample.
- § Total Lead Result has been rounded to two significant figures to reflect analytical precision.
- ‡ A "Version" indicated by -"x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

EMLab P&K, LLC

^{*}Sample preparation and analytical methods are based upon NIOSH 7082 and EPA 7000B.

Terracon

E-MAIL RE	PORT TO: PROJEC	T MANAGER (PM)	I FAD DAINT SAME	4 2 2 2 2 2
denise waller Engineerin	@terracon.com g Assistant	eric.dver@terracon.com Engineering Assistant	* Lead Analysis Flame AA (EPA 7420)	TTLC
□PM = \$ spsteinen@tr	S. Steiner steiner serracon.com	kmschroeter@terracon.com		AGE
PM – K. Pilgrir kmpilgrim@terracon.	n DPM- M. Ben	efield DPM - W. Frieszel acon.com wmfrieszell@terracon.c		□ PM – D. Block d.block@terracon.com
	ddress/Building No.		05pfa/14/1 East 3/6+ 3	Treet/Oakh
Sample(s) sent to:		Sampled By: John	Quantem Other Fully	: 5/1//20
TAT R		☑ 48HRS ☐ 3-5 Day	PETITAL Y	
Sample ID		Paint Description and	Sample Location	Condition (I/F/P)
01 1	Paint Beige	Substrate: Conc	were Component: Wall	
V - 1 1	Sample Location: Bl	dg #	Unit # Room Valle cito	P
	Paint Color:	Substrate:	Component:	
	Sample Location: Bl	dg #	Unit # Room	
	Paint Color:	Substrate:	Component:	
	Sample Location: Blo	dg #	Unit # Room	
	Paint Color:	Substrate:	Component:	
	Sample Location: Blo	dg #	Unit # Room	00240
	Paint Color:	Substrate:	Component:	02403937
	Sample Location: Blo	lg# (Jnit # Room	
Relinquished By:	J. Aleta	Signature:	Date/Time:	slilho
Received By:	2	Signature:	Date/Time:	5/1/20 123
Received By:	J. Timmony	Signature:	Date/Time:	112/20709:3



Appendix 3:

Material and Sample Location Drawing



Asbestos was not detected in the sampled materials. Lead was not detected in the sampled materials above the laboratory detection limit.



Vanir Construction

Highland Hospital

1411 East 31st Street

Building K


Oakland, California

Sample and Material Locations

<u>Date</u>	<u>Drafted By</u>
June 2020	ALC
Project Number R1197G03	Checked By KMS

Sheet Name Floor 4

Sheet Number



Asbestos was not detected in the sampled materials.

Lead was not detected in the sampled materials above the laboratory detection limit.



Vanir Construction
Highland Hospital

1411 East 31st Street

Building K


Oakland, California

Sample and Material Locations

Drafted By
ALC
Checked By
KMS

Sheet Name Floor 5

Sheet Number



Asbestos was not detected in the sampled materials. Lead was not detected in the sampled materials above the laboratory detection limit.



Vanir Construction

Highland Hospital

1411 East 31st Street

Building K


Oakland, California

Sample and Material Locations

<u>Date</u>	<u>Drafted By</u>
June 2020	ALC
<u>Project Number</u>	Checked By
R1197G03	KMS

Sheet Name Floor 6

Sheet Number



Asbestos was not detected in the sampled materials. Lead was not detected in the sampled materials above the laboratory detection limit.



Vanir Construction

Highland Hospital

1411 East 31st Street

Building K

Oakland, California

Sample and Material Locations

Date
June 2020
ALC

Project Number
R1197G03
Checked By
KMS

Sheet Name Floor 8

Sheet Number



Appendix 4:

Site Inspector Certificate

State of California Division of Occupational Safety and Health Certified Asbestos Consultant

John W Alexander

Certification No. 07-4296
Expires on 02/21/24

This certification was issued by the Division of Occupational Seight and Health as authorized by Sections 7130 at see 1st the Business and Professions Code.



STATE OF CALIFORNIA DEPARTMENT OF PUBLIC HEALTH



LEAD-RELATED CONSTRUCTION CERTIFICATE

INDIVIDUAL:

CERTIFICATE TYPE:

NUMBER:

EXPIRATION DATE:

Lead Inspector/Assessor Lead Project Monitor LRC-00004446

2/18/2021

LRC-00004445

2/18/2021

John Alexander

Disclaimer: This document alone should not be relied upon to confirm certification status. Compare the individual's photo and name to another valid form of government issued photo identification. Verify the individual's certification status by searching for Lead-Related Construction Professionals at www.cdph.ca.gov/programs/clppb or calling (800) 597-LEAD.

Limited Asbestos & Lead Survey Report

Highland Hospital
1411 East 31st Street
Koret Building
Oakland, California

June 17, 2020 Terracon Project No. R1207159

Prepared for:

Cymbre Potter
Vanir Construction Management, Inc.
1411 East 31st Street B1 Office
Oakland, CA 94602

Prepared by:

Terracon Consultants, Inc. 1466 66th Street Emeryville, California 94608 510-547-7771

Report Prepared by:		Annabelle Call
	Industrial Hygienist, CAC # 12-4856	
Report Reviewed by:	Karin Schroete	Karin Schroete
	Project Manager CAC #92-0772, CDPH #2228	

Offices Nationwide Employee-Owned Established in 1965 terracon.com



Table of Contents

1.	Executive Summary	. 1
2.	Scope of Work	. 1
	Asbestos Sample Results	
	Lead Sample Results	
	Limitations	
5.	Limitations	. 3

Appendices

- 1. Laboratory Results and Chain of Custody Asbestos
- 2. Laboratory Results and Chain of Custody Lead
- 3. Material and Sample Location Drawing
- 4. Site Inspector Certificate

Limited Asbestos & Lead Survey Report

Vanir Construction Management, Inc. Highland Hospital 1411 East 31st Street Koret Building Oakland, California

1. Executive Summary

The following is a report of a limited asbestos and lead survey conducted by John Alexander, Certified Asbestos Consultant (CAC) and California Department of Public Health (CDPH) Lead Inspector/Assessor with Terracon Consultants, Inc. (Terracon). The survey was performed on May 11, 2020 on the 4th floor of Koret Building of Highland Hospital located in Oakland, California.

Terracon was asked to limit the sampling to the materials that would be impacted by the scheduled installation of an emergency exhaust fan within the waiting room. No other suspect materials were sampled during this survey event.

Two (2) homogeneous suspect asbestos-containing materials (ACMs) were identified in the location where the exhaust vent was scheduled to be installed. The samples were analyzed using polarized light microscopy (PLM) techniques in accordance with methodology approved by the U.S. Environmental Protection Agency (EPA). As set forth in the Code of Federal Regulations, 40 CFR Part 763, Appendix A to Subpart F, Section 1.2 and 1.7.2.4, the lower limit of reliability detection for asbestos using the PLM method is approximately one percent (1%) by volume. Asbestos was not detected in the sampled materials.

Two (2) paint samples were analyzed for lead content. Lead was detected in one (1) of the samples.

2. Scope of Work

The scope of the survey was as follows:

- Collect samples of suspect ACMs that will be impacted by the scheduled work in the 4th floor lobby and at the building exterior.
- Collect a representative number of samples of suspect ACMs following a National Emissions Standards for Hazardous Air Pollutants (NESHAPS) protocol for sample collection. Asbestos

Limited Asbestos and Lead Survey Report Vanir Construction Management, Inc. Highland Hospital 1411 East 31st Street Koret Building Oakland, California

bulk samples were analyzed using polarized light microscopy (PLM) in accordance with EPA's July 1993 method for the determination of asbestos in bulk building materials - EPA 600/R-93/116.

- Collect samples of building materials suspected to be lead containing for purposes of compliance with California Department of Occupational Safety and Health (DOSH) Lead in Construction Standard. Lead samples were analyzed at an accredited laboratory by Flame Atomic Absorption (AA) for Total Lead reported in parts per million (ppm).
- Submit written report including analytical results and conclusions.

3. Asbestos Sample Results

Samples were collected of suspect interior and exterior building materials. Asbestos was not detected in the sampled materials. A summary of the sample results is provided in the following tables.

TABLE I NON-ASBESTOS CONTAINING MATERIALS

Material Description	General Sample Locations	Sample Results
I Wallboard with Taning Mud	ED Lobby 4 th Floor 4002 Wall ED Lobby 4 th Floor 4002 Back Side Wall	None Detected
Stucco	4 th Floor Staff Courtyard Wall	None Detected

Any additional materials found during construction activities and not identified in this survey report should be assumed to be ACM.

4. Lead Sample Results

Two (2) paint samples were submitted for lead analysis. The samples were analyzed for lead content using the Flame Atomic Absorption spectroscopy in accordance to EPA Method SW846-3050B-7420. When "<" appears in the lead sample report, it should be interpreted as meaning below analytical detection limit.

One (1) of the samples contained lead in detectable concentrations. The sample results are listed in Table II below.

Limited Asbestos and Lead Survey Report Vanir Construction Management, Inc. Highland Hospital 1411 East 31st Street Koret Building Oakland, California

TABLE II LEAD IN PAINT

Sample Number	Description/Location of Sample	Results mg/kg (ppm)
Pb-1	Off-White Paint on Wallboard / 4 th Floor ED Lobby	<47 ppm
Pb-2	Beige Paint on Stucco / 4th Floor Staff Courtyard	41 ppm

mg/kg - milligrams per kilogram, ppm - parts per million

5. Limitations

Our services consist of professional opinions, conclusions and recommendations that are made in accordance with generally accepted consulting standards, principles and practices. Reasonable attempts have been made to ensure that the report is complete and accurate with respect to Terracon's authorized scope of work. Terracon assumes no liability for damages, which might result from errors contained in the report or conditions, which the report fails to disclose. The quantity of samples, sample locations, and analyses performed were selected to provide analytical data to document and evaluate current site conditions.

The information provided in this report is not intended to be used as a biddable document for abatement purposes.



Laboratory Results and Chain of Custody - Asbestos





Report for:

Eric Dyer, Ms. Karin Schroeter Terracon Consultants, Inc. - Emeryville 1466 66th Street Emeryville, CA 94608

Regarding: Project: R1207159; Highland Hospital/1411 East 31st St./Oakland, CA.

EML ID: 2403936

Approved by:

Dates of Analysis: Asbestos PLM: 05-13-2020

Approved Signatory Amin Suliman

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267) NVLAP Lab Code 200728-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins EMLab P&K ("the Company") shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Eurofins EMLab P&K

6000 Shoreline Ct, Ste 205, So. San Francisco, CA 94080

Client: Terracon Consultants, Inc. - Emeryville

(866) 888-6653 Fax (623) 780-7695 www.emlab.com

C/O: Eric Dyer, Ms. Karin Schroeter

Re: R1207159; Highland Hospital/1411 East 31st St./ Date of Receipt: 05-11-2020
Oakland, CA.

Date of Report: 05-13-2020

ASBESTOS PLM REPORT

Total Samples Submitted: 6
Total Samples Analyzed: 6
Total Samples with Layer Asbestos Content > 1%: 0

Location: 1A, Wallboard with taping mud; ED lobby 4th floor 40002 wall

Sample Layers

White Compound

Cream Tape

White Joint Compound

White Drywall with Brown Paper

Lab ID-Version‡: 11464620-1

Asbestos Content

ND

ND

ND

ND

ND

ND

Composite Non-Asbestos Content: 15% Cellulose **Sample Composite Homogeneity:** Poor

Location: 1B, Wallboard with taping mud; ED lobby 4th floor 40002 back side wall

Lab ID-Version‡: 11464621-1

Sample Layers	Asbestos Content
White Joint Compound	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	15% Cellulose
Sample Composite Homogeneity:	Poor

Location: 1C, Wallboard with taping mud; ED lobby 4th floor 40002 back side wall

Lab ID-Version 11464622-1

Sample Layers	Asbestos Content
White Joint Compound	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	15% Cellulose
Sample Composite Homogeneity:	Poor

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. Eurofins EMLab P&K reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by -"x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Eurofins EMLab P&K

Lab ID-Version‡: 11464623-1

Lab ID-Version 1: 11464624-1

Lab ID-Version 1: 11464625-1

6000 Shoreline Ct, Ste 205, So. San Francisco, CA 94080

Client: Terracon Consultants, Inc. - Emeryville

(866) 888-6653 Fax (623) 780-7695 www.emlab.com

C/O: Eric Dyer, Ms. Karin Schroeter Date of Sampling: 05-11-2020 Re: R1207159; Highland Hospital/1411 East 31st St./ Date of Receipt: 05-11-2020 Oakland, CA. Date of Report: 05-13-2020

ASBESTOS PLM REPORT

Location: 2A, Stucco; 4th floor staff courtvard wall

Sample Layers	Asbestos Content
White Skim Coat	ND
Gray Stucco	ND
Sample Composite Homogeneity:	Moderate

Location: 2B. Stucco: 4th floor staff courtvard wall

20 carron 22, Staces, 1th host stail courty and wan	•
Sample Layers	Asbestos Content
White Skim Coat	ND
Gray Stucco	ND
Sample Composite Homogeneity:	Moderate

Location: 2C. Stucco: 4th floor staff courtvard wall

Sample Layers	Asbestos Content
White Skim Coat	ND
Gray Stucco	ND
Sample Composite Homogeneity:	Moderate

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. Eurofins EMLab P&K reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

 \ddagger A "Version" indicated by -"x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Terracon

***E-MAIL PM - S. Ste spsteiner@terraci PM- M. Bene msbenefield@terra PM- D. Bkc David.block@terra	con.com kmschroeter@terracon.com kmplkgrim@terracon.com efield	PLM Analysis (Analyze all samples) Stop Analysis at First Positive Point Count Analysis (400-point)
	dress/ Building No. High and Hospital 1911 195	- 3/st Street / Oakland, CA
roject# R	-07 59 Sampled By: Akrander	Sampling Date: 5/11/20
ample(s) sent to:	☐ MAL ☐ ASB TEM ☐ EMLAB ☐ Other _	
AT Rush	□ 24HRS □ 48HR □ 3-5 days	
HM#	Material Description Wallboam with Tap	the Myd
Sample ID	Sample Location & Material Location	Quantity:
IA	ED Lobby 4th Floor 4002	Wall
IR	EN Lohou 4th Floor 4002	Back Side, Wall,
IC.	EN Luby 4th Floor 4002	Buck Side Wall
HM# 1	Material Description: Stucco	
Sample ID	Sample Location & Material Location	Quantity:
2.4	All of of Company	1 Wall
28	the Floor State Countyard	1 , 1
20	The Floor Part Countygro	Wall
HM#		
Sample ID	Material Description: Sample Location & Material Location	Quantity:
HM#	Material Description:	Quantity:
Sample ID	Sample Location & Material Location	Quantity.
		002403
HM#	Material Description:	Quantity:
Sample ID	Sample Location & Material Location	Quantity:
Relinquished By	: J. Alexander Signature: Jelle U.	Date/Time: 5/1/20
Received By:	Signature:	Date/ Time: 3/11/20
Relinquished By	: Signature:	Date/Time:
Deceived Rv	Signature:	Date/Time:



Laboratory Results and Chain of Custody - Lead





Report for:

Eric Dyer, Ms. Karin Schroeter Terracon Consultants, Inc. - Emeryville 1466 66th Street Emeryville, CA 94608

Regarding: Project: R1207159; Highland Hospital, 1411 East 31st Street, Oakland, CA

EML ID: 2403939

Approved by:

Technical Manager Andrew Ikeda

Indus Heda

Dates of Analysis:

Lead - Flame AA: 05-12-2020

Service SOPs: Lead - Flame AA (EM-BC-S-8443) AIHA-LAP, LLC accredited service, Lab ID #178697

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. Due to the nature of the analyses performed, field blank correction of results is not applied. The results relate only to the samples as received. Sample size, as it relates to Wipe samples only, is supplied by the client.

Eurofins EMLab P&K ("the Company") shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Eurofins EMLab P&K's LabServe® reporting system includes automated fail-safes to ensure that all AIHA-LAP, LLC quality requirements are met and notifications are added to reports when any quality steps remain pending.

Eurofins EMLab P&K

17461 Derian Ave, Suite 100, Irvine, CA 92614

(866) 888-6653 Fax (623) 780-7695 www.emlab.com

Client: Terracon Consultants, Inc. - Emeryville

C/O: Eric Dyer, Ms. Karin Schroeter

Re: R1207159; Highland Hospital, 1411 East 31st Street, Oakland, CA

Date of Sampling: 05-11-2020 Date of Receipt: 05-11-2020 Date of Report: 05-13-2020

LEAD: FLAME ATOMIC ABSORPTION SPECTROMETRY

Location:	Pb-1:	Pb-2:
	Off-white wallboard wall, ED lobby,	Beige stucco wall, 4th floor staff
	4th	courtyard
	floor	
Comments (see below)	A	A
Lab ID-Version‡:	11464351-1	11464352-1
Analysis Date:	05/12/2020	05/12/2020
Sample type	Paint Chip sample	Paint Chip sample
Method*	NIOSH 7082 & EPA 7000B modified	NIOSH 7082 & EPA 7000B modified
† Method Reporting Limit	47 ppm	39 ppm
Sample size	0.2133 grams	0.2577 grams
§Total Lead Result	< 47 ppm	41 ppm

Comments: A) The relative percent difference of the matrix duplicate pair was above control limits. The laboratory control sample and matrix blank were both within control limits and validated the batch.

Sample results have not been corrected for blank values.

Bulk samples are not covered under the AIHA-LAP, LLC service accreditation.

Wipe samples must meet ASTM E1792 criteria. Method Reporting Limits may not be valid for non-ASTM E1792 wipe samples.

- † The Method Reporting Limit is the minimum concentration of Lead that the laboratory can confidently detect in the sample.
- § Total Lead Result has been rounded to two significant figures to reflect analytical precision.
- ‡ A "Version" indicated by -"x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

EMLab P&K, LLC


^{*}Sample preparation and analytical methods are based upon NIOSH 7082 and EPA 7000B.

Tierracon

E-MAIL REPO	ORT TO: PROJE	CT MANAGER (F	PM)*	LEAD PA	AINT SAM	IPLE DATA SHEET		
denise.wallen@terracon.com Engineering Assistant		eric.dver@iterracon.com Engineering Assistant			* Lead Analysis Flame AA (EPA 7420) TTLC			
	□PM – S. Steiner spsteinen@terracon.com kr		Schroeter erracon.com		PAGEOF			
PM – K. Pilgrim kmpilgrim@terracon.cc								
	address/Building No	Sampled By:	J. Hosy	atal/1411 Ea Aktanden	st 31st. Sampling	Sheet / Ogklang Date: 5/11/20		
Sample(s) sent to:		1	iology 🔲 Q	Quantem Other	Emlab			
Sample ID		Paint Descr	iption and S	Sample Location		Condition (I/F/P)		
0) [Paint OF-W	hile Substr	ate: Wall	Compone	ent: Wall			
Pp-	Sample Location:	Bldg #		Unit#	Room Fly	bby fr		
2) 2	Paint Belg	Substr	ate: Stu	CC / Compone	ent: Wal	1		
10	Sample Location:	Bldg #		Unit #	Room Hh	Floor		
	Paint Color:	Substr	ate:	Compone	ent:			
	Sample Location:	Bldg #		Unit #	Room			
	Paint Color:	Substr	ate:	Compone	ent:	00		
	Sample Location:	Bldg #		Unit #	Room	. 11		
	Paint Color:	Substr	ate:	Compone	ent:	403939		
	Sample Location:	Bldg #	- 100 · ·	Unit #	Room			
Relinquished By		h (er Sign	nature:	9/1/	Date/Tin	s/1/20 1721		
Received By:	200		nature:		Date/ Tir	0/11/60 1001		
Received By:	J. Tilmin	Sig	nature:	110-	Date/Tin	0/1/20 1.29		



Material and Sample Location Drawing



The following materials are not depicted:

• Lead containing beige paint (41 ppm) on stucco wall at 4th floor staff courtyard

Asbestos was not detected in the sampled materials.



Vanir Construction Management

Highland Hospital

1141 East 31st Street

Koret Building

Oakland, California

Sample and Material Locations

<u>Date</u>	<u>Drafted By</u>
June 2020	ESD
<u>Project Number</u>	Checked By
R1207159	KMS

Sheet Name 4th Floor

Sheet Number

Figure 1



Site Inspector Certificate

State of California Division of Occupational Safety and Health Certified Asbestos Consultant

John W Alexander

Certification No. 07-4296
Expires on 02/21/24

This certification was issued by the Division of Occupational Seight and Health as authorized by Sections 7130 at see 1st the Business and Professions Code.