



**Job Order Contract**  
**Request For Proposal**

---

**Date Issued:** 07/21/16

**Date Printed:** 07/20/16

**To:** Joshua Lee  
MTM Construction  
16035 Phoenix Dr  
City of Industry, CA 91745  
**Phone:** (626) 934-1112

**From:** Monty Boyd

**Phone:** 510.667.3038

**Project Title:** SRJ Main Parking Lot Repair

<b>Job Order No:</b> 15012-17008.0
------------------------------------

---

Alameda County General Services Agency requests that you provide a Cost Proposal for the subject Job Order per the Scope of Work.

The following document is to be Exported through PROGEN by the Contractor electronically:

1. Contractor Cost Proposal

Hard copies of the following documents are to be signed and delivered by the Contractor:

1. Contractor Cost Proposal
2. Construction Duration Schedule
3. Backup for Non-Prepriced Line Items
4. Material or Equipment Submittals (if required by PM in advance of issuance of the Job Order)

**Additional Requirements:**

**Liquidated Damages:** WILL NOT APPLY

This request is subject to the terms and conditions of JOC Contract: 15012. Please refer to the attached Scope of Work for additional information.

**Your proposal is due on or before 08/12/2016.**

Note: Contractor to notify PM immediately if due date cannot be met.

Attachment: Scope of Work



## Job Order Contract

### Detailed Scope of Work

---

**Date:** July 20, 2016 7:17 pm  
**Work Order No.:** 15012-17008.0  
**Work Order Name:** SRJ Main Parking Lot Repair  
**Location:** 5325 Broder Blvd. Dublin CA  
**Brief Scope:** Parking lot upgrades for SRJ Main Parking Lot  
See KTA Progress Drawings Dated 6.16.16 (Pages A.1, A.2 and A.3)  
Please bid: ADA, East Side and West Side separately

#### ADA Upgrades (East Side Only)

- Remove and replace sidewalk for ADA access as supplied on progress drawings
- Area includes catch basin and re-slope to existing sidewalk/ramp
- Remove and replace existing asphalt paving where indicated on KTA drawings
- Restripe parking lot with ADA supplied specifications
- Install new post and handicap signs (2) handicap van and (10) handicap to include with minimum fine \$250 in front of each appropriate Handicap stalls - Final drawings pending

#### East Side of Parking Lot:

- Repair to parking lot areas that require replacement of asphalt - areas TBD with job site walk
- Seal smaller cracks as necessary for paving - Seal coat entire lot - Restripe all existing pavement markings as per present layout. - Install 9"by 30" Thermo Plastic Storm Drain Marking, NO DUMPING FLOW TO BAY, with Fish at new trench drain, locations to be field verified - Install 9"by 30" Thermo Plastic Storm Drain Marking, NO DUMPING FLOW TO BAY, with Fish at each (E) storm water drainage location within the parking lot

#### West Side of Parking (provide alternate pricing):

- Repair to parking lot areas that require replacement of asphalt - areas TBD with job site walk
- Seal smaller cracks as necessary for paving
- Seal coat entire lot
- Restripe all existing pavement markings as per present layout.
- Install 9"by 30" Thermo Plastic Storm Drain Marking, NO DUMPING FLOW TO BAY, with Fish at new trench drain, locations to be field verified
- Install 9"by 30" Thermo Plastic Storm Drain Marking, NO DUMPING FLOW TO BAY, with Fish at each (E) storm water drainage location within the parking lot

---

The following items detail the scope of work as discussed at the site. All requirements necessary to accomplish the items set forth below shall be considered part of this scope of work: